Sr.No	RFP Section	RFP Requirement Statement	Questions	Response by MTC
	Term of Reference - Technical	Should have Manual Bypass switch	Is this an additional External Manual Bypass, or does it refer to internal Maintenance Bypass of UPS	No need for external bypass
	Term of Reference - Technical	Additionally, we should mention that the cabling must be included.	How much cabling is required. A standard length for all to quote on will be great, and also if cable management like cable trays are required.	Beneath the UPS is a cable trench. Cable length can differ if it top feed or bottom feed. For bottom feed it can be 2 x 6meter =12m per UPS. To be more accurate on the length the tenderer/s can arrange onsite meeting.
	Term of Reference - Technical		Do you want 2x 400Kva UPS systems or 2x 400kva frame UPS with 200kva moduals each	We need 2x 400KVA UPS
	TENDER FORMAT		Do you require both a soft and hardcopy submission or either or will do	Both are required